

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Schoolcraft Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. <u>W.</u> , R. <u>13</u> <u>W.</u>	F-10
2. PROPERTY CONTROLLING IN SECTION <u>28</u>	, T. <u>44</u> N. <u>W.</u> , R. <u>13</u> <u>W.</u>	9
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 2-18, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- F-10 Center corner of section 28. Not prev. est.
9 East 1/16 corner of section 28. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-10 Corner set at intersection of north - South and East - West 1/4 lines.
9 Corner set M.P.O.L. between center corner and east 1/4 corner of section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Mont. set at both corners. Bearings:

- | | |
|------------------------------|----------------------------|
| F-10 6" Spruce, N50°W, 30.8' | 9 6" H. Maple, S33°W, 9.2' |
| 7" Spruce, N03°E, 30.4' | 8" H. Maple, N79°W, 12.3' |
| 12" Spruce, N71°E, 28.1' | 10" H. Maple, N27°W, 16.1' |
| 12" Spruce, S30°E, 18.3' | 14" Cedar, N60°E, 21.4' |

SIGNED BY

David E. Babbitt

David E. Babbitt

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

DATE 3-16-83

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: