

16

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

(County)	Located in:	Corner Code #
1. Public Land Survey	T 44N R 13W	C5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 20 T 44N R 13W	2
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on June 01, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C5) Section corner common to Sections 7-8-17-18. Original corner established by U.S. Deputy Surveyor Guy M. Carleton, 1850. Original B's: Ironwood 10 N38E 27 links, Hemlock 14 S40W 52 links. Corner subsequently monumented by U.S. Biological Survey ca. 1936 with a brass capped concrete post. USBS record (Book 29, page 6, dated April 29, 1937, U.S. Fish and Wildlife Service, Minneapolis, MN.) does not mention original evidence. New accessories are noted as follows: 12" Balsam N27E 0.45 ch. "BTS8744NR13W, 8" Maple N68W 0.33 ch. "BTS7744NR13W. Also noted: "The cor in fc. cor. fences N-E-W in hardwood timber 0.38 ch. W of centerline dirt road bears E and W 4+/- ch thence S." U.S. Dept of Interior, Bureau of Sport Fisheries and Wildlife records (Survey of Stearns Coal and Lumber Company Tract Dec. 8, 1960, and field notes B. 32, Pg. 19 Oct. 13, 1960) show this mon. was recovered and a 5/8" I.P. was set 1" below surface in the c/l of graded E-W road, on the section line S0° 12' W, 0.38 ch. from the corner. Found no subsequent record.

(2-Sec. 20) East 1/16 corner between sections 17-20. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C5) Original post and accessories not recovered, USBS post and 1936 wits. not recovered. Found 5/8" pinched pipe in c/l of E-W rd, approx. 4 chains east of turn to south in accord with 1960 record and believe it to be the I.P. placed in 1960. The corner itself appears to have been destroyed by ditch construction. I reestablished the corner by projecting a line through the USBS 1/4 corner between 18/17 and the pinched pipe to a point 0.38 ch. (25.08') north of the pipe, this point being in the ditch. This position is in accord with USBS measurements to corners north, east and south. With difficulty, I retraced the old fence line going west from the corner. It is nearly gone, with only bits of scattered wire, and rotted post remains. The projection of this fence appears to fall about 12' south of the corner. No fence was observed to the north, or to the east. Although the distance south to the 1/4 corner is nearly 1/2 chain longer than the original record and the maintained road centerline is 25' south of the corner, I accepted and monumented the USBS position as the best available evidence of the original corner. At the position for the corner, I drove a 1"x32" iron pipe capped with a yellow plastic cap stamped "Mich DNR LS 3398a" to ground surface.

(2-Sec. 20) Found no evidence of prior monumentation or evidence of use at corner location. Established the corner midway and on a straight line between monumented 1/4 corner 1314.70' west and monumented section corner 1314.70' east. At the position for the corner, placed a 1" iron pipe capped with a 4" dia. cast aluminum MNR tablet, appropriately stamped

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C5) Set 1"x32" pipe with plastic cap. Blazed, scribed, and set measuring nails and tags in the following new bearing trees:
10" w. Birch S02E 62.3' "S17 NBT"
Power pole N76W 68.1'
12" Maple N02W 39.1' "S7 NBT"
fence post N07E 31.7'
Fd. 5/8" pipe in c/l road S05W 25.08'
bearings are magnetic.



(2-Sec. 20) Set 1" pipe with 4" aluminum cap. Blazed, scribed, and placed measuring nails in the following bearing trees:
8" Cedar S53E 6.5' "1/16S BT"
5" Cedar S25E 3.2' "1/16S BT"
8" Cedar N70W 2.7' "1/16S BT"
10" Cedar twin N12W 3.25' "1/16S BT"
Placed 6" squared cedar post adjacent.

Signed by Stephan J. Szyszkoski

Date 6-24-93

Surveyor's Michigan License No. 33986