

21

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft County	Located In:	Corner Code #
1. Public Land Survey	T 44N R 13M	E8
	T 44N R 13M	E9
	T R	
	T R	
2. Property Controlling in Section	S 17 T 44N R 13M	10
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

10 June 02, 1993

E9 May 25, 1993

I, Stephan J. Szyszkoski, in a field survey on E8 May 25, 1993, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- (E8) Quarter corner common to Sections 20-21. Original corner established by U.S. Deputy Surveyor Guy M. Carleton, 1850. Original Bts: Sugar 10 S40W 15 links, Ironwood 8 N72E 41 links. Found no subsequent record.  
(E9) Section corner common to Sections 20-21-28-29. Corner previously recorded by David B. Babbitt RLS, in 1983 as follows: "1" pipe with plastic R.L.S. cap buried at intersection of roads North and East. New bearings: Tag in 18" W. maple S70W 51.9', tag in 10" W. Birch S29W 43.85', tag in power pole S31E 33.2'.  
(10-Sec. 17) South 1/16 corner between sections 18/17. Corner not established in the original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (E8) Original post and accessories not recovered. Found no evidence of prior monumentation and no acceptable evidence of the position of the original corner. Reestablished the corner by single proportionate measurement to the original record between monumented section corners 2641.50' north and south. At the position for the corner, I placed a 1"x32" iron pipe capped with a 4" cast aluminum MDNR tablet, appropriately stamped.  
(E9) Found and accepted Babbitt's 1" capped pipe, buried beneath the ground surface in good condition. All 1983 witnesses are still in place and at record bearing and distance from the monument with the exception of the 18" W. Maple, which has been cut. Marked additional witnesses as shown below.  
(10-Sec. 17) Found no evidence of prior monumentation or evidence of use at corner location. Established the corner midway and on a straight line between monumented 1/4 corner 1321.48' north and monumented section corner 1321.48' south. At the position for the corner, placed a 1"x32" iron pipe capped with a 4" cast aluminum MDNR tablet, appropriately stamped.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |  |  |
|---|--|--|
| (E8) Set 1" pipe with 4" aluminum cap. Blazed, scribed, and set measuring nails with tags in the following new bearing trees: | (E9) found 1" iron pipe with yellow plastic R.L.S. cap. Distances shown below are to measuring nails with tags. Bearings are magnetic. | (10-Sec. 17) Set 1" pipe with 4" cap. Blazed, scribed, and set measuring nails in the following bearing trees: |
| 5" Cedar N25W 44.55' "1/4S NBT"   | 19" W. Birch, S29W 43.85'  | 12" Jack Pine S89E 11.8' "1/16S BT"  |
| 6" Cedar N19W 54.95' "1/4S NBT"   | Power pole S31E 33.2'  | 10" Jack Pine S08E 7.5' "1/16S BT"   |
| 5" Maple S55E 19.7' "1/4S NBT"  | 6" Elm N25W 51.8' "S20 NB"   | 4" Spruce S01E 24.45' "1/16S BT"   |
| 14" Spruce S50W 26.0' "1/4S NBT"  | fence post S49E 49.1'  | 10" Jack Pine S08W 31.0' "1/16S BT"  |
|   |  | placed a 5" squared cedar post adjacent. Bearings magnetic.  |

Signed by

*Stephan J. Szyszkoski*

STEPHAN J.

SZYSZKOSKI

LAND

SURVEYOR

No.

33986

6-24-93

Surveyor's Michigan License No. 33986