

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft

(County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|-------------|---------------------------|-----------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S <u>32</u> | T <u>44N</u> R <u>13W</u> | <u>13</u> |
| | S <u>32</u> | T <u>44N</u> R <u>13W</u> | <u>9</u> |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Mar 12 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:
 (13-Sec. 32) Southeast 1/16 corner. Not established in the original survey.
 (9-Sec. 32) East 1/16 corner, Section 32. Not established in the original survey.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (13-Sec. 32) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (9-Sec. 32) Established the corner midway and on a straight line between Quarter corner 1316.75' east and Center of Section (unmonumented intersection of 1/4 lines) 1316.75' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
14" Maple N18E 19.75' "SE1/16 BT"
8" Maple S20E 19.35' do
10" Maple S56E 8.5' do
10" Maple S71W 23.5' do
Placed cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (9) Set 1"IDx36" I.pipe with yellow plastic cap #33986 at the corner, which falls in the center of a N-S trail road. Blazed, scribed and set measuring nails in:
12" Balsam S56W 9.4' "E1/16 BT"
5" Balsam S31W 12.8' do
8" Balsam N43E 15.7' do
6" Balsam N18W 38.8' do
Bearings are magnetic. Distances are to nail with tag. |
|--|--|



Signed by Stephan J. Szyszkoski Date 4/16/02
 Surveyor's Michigan License No. 33986