

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 44 N. R. 15 & 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER North 1/16 for Secs. 13, T44N R16W and 18, T44N R15W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/26/64 by A.O. Enger, Monumented and recorded
5/26/65 Bray and Hinds

WITNESSES TO CORNER..... 7" Balsam (1/16S BT), S 30° W, 19 Dcs.



7" Balsam (1/16BT), N 70° W, 10 1/2 Dcs.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set midway and on line between 1/4 Corner 19.985 chs South and Section Corner the same distance North.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965
REGISTERED LAND SURVEYOR