

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 15 & 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 12/13 T44N R16W and 7/18 T44N R15W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

8/26/64 by A.O. Eger, Monumented and recorded 5/26/65
DATE MONUMENT PLACED AND WITNESSED by Bray and Hinds.

WITNESSES TO CORNER..... 7" Balsam (S7 NBT), N 72° E, 45 Lks.



9" W. Spruce (S12 NBT, N 18° W 74 Lks.

8" Aspen (S13 NBT), S 50° W, 17 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set from White Pine 40" N 35° E, 18 Lks, BT Stump. Checks with line and stream crossing on transit line. Original Corner 79.94 chs South.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965
REGISTERED LAND SURVEYOR