

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION



# LAND CORNER RECORD


T. 44 N.R. 15 & 16 W

Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Secs. 13, T44N R16W and 18, T44N R15W.

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap  
1/15/64 by A.O. Enger -- recorded and monumented 5/20/65  
DATE MONUMENT PLACED AND WITNESSED by Bray and Hinds.

WITNESSES TO CORNER..... 30" W. Pine Stump (1/4S NBT), N 45° E, 100 Lks.



4" Balsam (1/4S NBT), N 42° E, 104 1/2 Lks.

6" Aspen (1/4S NBT), N 04 1/2° E, 142 1/2 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set midway and on line between Section Corners 39.97 Chs., to North and to South. Corner is 9.14 Chs. North of Line tree as given in Original notes, and 5.98 Chs North of south bank of stream (Original Notes as 6.00 Chs.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965  
REGISTERED LAND SURVEYOR