

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 15 & 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER S 1/16 Corner for Secs. 13, T44N R16E and 18, T44N R15W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 1/16/64 by A.O. Enger, recorded and monumented by
Bray and Hinds

WITNESSES TO CORNER..... 30" W. Pine Stump (1/16S NBT), N 00 $\frac{1}{2}$ ^o W, 14 Lks.



5" Balsam (1/16S NBT), N 64^o E, 73 Lks.

8" Aspen (1/16S NBT), S 37^o W, 16 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed midway and on line between 1/4 Corner 19.985 North and Section Corner same distance South, also checks well with stream and line tree to North.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965
REGISTERED LAND SURVEYOR