

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 15 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 19-20-29-30

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/20/65 recorded and monumented Bray and Hinds

WITNESSES TO CORNER..... 14" Red Pine (S30 NBT), S 69 $\frac{1}{2}$ ^o W, 06 $\frac{1}{2}$ Lks.



14" White Pine (S20 NBT), N 37^o E, 53 Lks.

6" Jack Pine (S29 NBT), S 78 $\frac{1}{2}$ ^o E, 18 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from down and burned remains of White Pine 12", S 58^o E, 35 Lks., BT with axe and part of scribe marks. Old rotted stake on ground at Corner. Stump bottom of other BT in proper position.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965
REGISTERED LAND SURVEYOR