

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N. R's 15 & 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner for sections T44N R16 W $\frac{24}{19}$ 25/30 T44N R15W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/29/69, F. J. Bray with M. Burnis

WITNESSES TO CORNER..... 5" Willow (in clump) (S.19) (NBT) N 83° E, 74 links



No other tree near.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and the single proportioned measurement between the town corner two miles south and 1/4 corner 1/2 mile to north.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/17/69
REGISTERED LAND SURVEYOR
Frank J. Bray