

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 15-16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner 18, 19, 13, 24

CORNER MONUMENT 2" I.D. iron pipe with 2 1/2" brass cap stamped "13, 24, 18, 19, c.c."

DATE MONUMENT PLACED AND WITNESSED Placed in 1949; re-witnessed 8/30/63

WITNESSES TO CORNER..... White Pine 16 N73E 28 1/2 links, "S18, NBT"



do 16 N35W 65 " "S13, NBT"

Red Maple 8 S63 1/2 E 38 " "S19, NBT"

AND

do 10 S48W 41 1/2 " "S24, NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner located and pipe set by Carl Christensen and Carl Makel from four original bearing trees, condition in 1964 as follows: White Pine 14 S75E 6 links, down poor condition, pieces of face with scribe marks found; White Pine 24 N45E 47 links, down, poor condition but upper face present; White Pine 24 S70W 38 links, a turned-over stump with only axe marks visible; and White Pine 36 N62W 33 links, a rotted stump bottom.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 9-17-64
REGISTERED LAND SURVEYOR
Arthur O. Enger
RLS 19542