

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 15W	A7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/10/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A7) Corner common to Sections 18-19 T44N-R15W and Sections 13-24 T44N-R16W. 1963 - Corner rewitnessed in 1963 and recorded in 1964 by A.O.Enger RLS, who found pipe set by Carl Christensen and Carl Makel from four original bearing trees in 1949. In his recordation certificate, Mr. Enger notes the condition of the 4 bearing trees as he found them. Corner monument is 2" I.D. iron pipe with 2.5" brass cap, stamped to identify the corner. 1963 witnesses: W.Pine 16" N73E 28.5 links, W.Pine 16" N35W 65 links, Red Maple 8" S63 1/2E 38 links, Red Maple 10" S48W 41.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A7) Found the Carl Christensen monument as described, in good condition, and at record bearing and distance from the 1963 witnesses. The W.Pine NE is in good condition, the W.Pine NW is standing dead. The R.Maple NBTs are now both stumps at record bearing and distance, no markings visible. The original BTs are now gone. Accepted the corner as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A7) Found 2"ID I. pipe with 2.5" brass cap. Set measuring nail with MDNR tag in the side of:
 24" W.Pine N80E 19.97' old blazes (1963 NBT)
 7" Maple N12E 19.35' mrkd "S18 NBT"
 14" twin Maple S59E 25.22' "S19 NBT"
 5" Balsam N62W 24.75' "S13 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 01/26/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities