

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Sections 27-26

CORNER MONUMENT 1" x 4" Iron Pipe

DATE MONUMENT PLACED AND WITNESSED 7/27/64 by A.O. Engel, 5/18/65 checked and recorded by
Bray and Hinds

WITNESSES TO CORNER..... 7" Jack Pine (1/4S NBT), S 55° E, 23 1/2 Links



9" Jack Pine (1/4S NBT), S 36° W, 26 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set from point of probable original post at the bearing and distance from BT (stump) Spruce pine 8 S 65° E, 14 lks; burned but part of Lower blaze and notch present.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965
REGISTERED LAND SURVEYOR