

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 44 & 45 N.R. 16 W

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 35, 34, T45N R16W
2, 3, T44N R16W

CORNER MONUMENT 2" x 4 1/2" Iron Pipe
DATE MONUMENT PLACED AND WITNESSED 11/4/63 by A.O. Enger - 5/19/65 by checked and recorded by Bray and Hinds.

WITNESSES TO CORNER..... 6" Red Maple (S2 NBT), S 61° E, 19 Lks.



6" Red Maple (S3 NBT), S 89° W, 29 Lks.

8" Y. Birch (S35 NBT), N 06° E, 16 Lks.

AND
11" Cedar (S34 NBT), N 29° W, 116 Lks.

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set from stump of Original BT, W. Pine 22" N 55° W, 32 Lks. which has lower blaze with scribe marks "BT" on it. Stump of BT, W. Pine 18 S 44° W 69 Lks. is also present. The Iron Pipe described above had been placed many years previously by an unknown surveyor, but not in place given in original notes. It had been set S 55° E, 15 Lks from NW BT and had following NBT's.
15" Red Maple (S35 BT), N 31° E, 35 Lks.
16" Red Maple (S3 BT), S 73° W, 96 1/2 Lks.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965
REGISTERED LAND SURVEYOR