

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S., R. <u>16</u> E. W.	<u>A-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 24 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Northwest section corner - Section 18; Wood Post, Bl. Ash 16 - N63°E - 32 lks.; Do 10 - S55°E - 57 lks.; Do 6 - S55°W - 8 lks.; searched thoroughly but found nothing.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Set from the calls in the notes of the original gov't survey, for a stream 1.29 chs. east and "leave bottomland" 3 chs. west. The measurement is about .70 chs. long to the stream north but there has been considerable beaver work in that area and it is all bottomland so the stream could easily have been that much farther south at the time of the original survey. Measurement east 1 mile from this position to a monument with O.B.T.'s in place is 4' short of record G.L.O. measurement. Measurement south 4 miles to the township corner is 14' long and north 2 miles to the township corner is 30' short.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" pipe, 4" aluminum cap; 12" J. Pine - S3°E - 112.7'; 5" Bl. Ash - S89°E - 28.4'; 9" Bl. Ash - N36°W - 39.6'; 12" J. Pine - S20°W - 112.4'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 6-26-80
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558