

SCHOOLCRAFT
LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} / _{S.} , R. <u>16</u> ^{E.} / _{W.}	<u>A-11, A-12, A-13</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S., R. _____, E./W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S., R. _____, E./W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on March 19 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- A-11 N.W. Section corner of Sec. 31; Wood Post, Y. Pine 10" - N15°E - 4.73 chs.; Spruce 6" - N22°W - 4.00 chs.; Spruce 8" - N14°E - 4.65 chs.; Spruce 7" - S24°E - 2.70 chs.
 - A-12 West 1/4 corner - Section 31; Wood Post, Maple 5" - S79°E - 13 lks.; Tamarack 8" - West - 7 lks.
 - A-13 S.W. section corner - Section 31; Wood Post; Tamarack 6" - S59°W - 86 lks.; Do 6" - N30°E - 177 lks.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- A-11 Set by single proportionate measurement from northwest corner of Section 18, north and southwest corner of Section 31 south. No sign of original evidence.
 - A-12 Set M.P.O.L. between northwest corner of Section 31 and southwest corner of Section 31. No sign of original evidence.
 - A-13 Set at record G.L.O. measurement west of the stub of the line tree recorded as "74.07 y. pine 12" on the south line of Sec. 31. One hack mark plain on this badly burned stub. Measurements North-South-East & West are reasonable. No sign of O.B.T.'s.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- ALL 1" pipe, 4" aluminum cap.
 - A-11 16" R. Pine - S20°W - 137.4'; 5" J. Pine - S15°E - 72.3'; 16" J. Pine - S77°W - 29.9'; 14" W. Pine - N14°W - 94.4'; Centerline N-S Ditch - West - 40'.
 - A-12 10" R. Pine - N1°W - 34.5'; 10" Twin W. Birch - N58°E - 20.0'; 14" R. Pine - N88°E - 10.1'; 10" Aspen - N34°W - 7.9'.
 - A-13 8" J. Pine - S71°W - 96.2'; 6" Poplar - N79°W - 31.35'; 12" Tw. J. Pine - N13°W - 61.7'; 4" Poplar - N1°E - 11.6'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 7-13-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558