

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 44 N. B. R. 16 W.	A-7, A-8, C-9
2. PROPERTY CONTROLLING IN SECTION _____	.T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	.T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on March 24 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- A-7 N.W. section corner of Section 19; Wood Post, N. Pine 6" - N81°E - 82 lks.; Spruce 5" - N73°W - 76 lks.; Tamarack 8" - S13°E - 64 lks.; Spruce Pine 3 - N52°E - 15 lks.
 - A-8 West 1/4 corner - Section 19; Wood Post, Tamarack 5" - N41°E - 73 lks.; Tamarack 5" - N55°W - 62 lks.
 - C-9 S.E. section corner - Section 19; Wood Post, Yellow Pine 16" - N59°W - 20 lks.; Spruce Pine 12" - S33°W - 84 lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- A-7 Set by single proportinate measurement from northwest corner of Sec. 18 north and southwest corner of Section 31 south.
 - A-8 Set M.P.O.L. between the N.W. corner of Sec. 19 and S.W. corner of Sec. 19. No sign of original evidence.
 - C-9 Set from Y. Pine stump remains of N.W. O.B.T. - measurements to swamps north 7.80 chs. - west 4.00 chs. and south 13.80 chs. are definite and exact. Measurement 1/2 mile east to the 1/4 corner common to sections 29 & 30 which has a living O.B.T., is good.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- ALL 1" pipe, 4" aluminum camp.
 - A-7 4" R. Pine - N1°W - 38.85'; 9" J. Pine - S4°E - 4.9'; 10" J. Pine - N46°W - 21.25'; 9" J. Pine - N70°E - 25.8'.
 - A-8 8" Spruce - N39°E - 56.7'; 6" Spruce - N1°W - 79.95'; 7" Spruce - N36°W - 99.0'; 5" Spruce S88°W - 67.55'.
 - C-9 6" R. Pine - N7°W - 33.7'; 7" R. Pine - N25°E - 35.0'; 4" Oak - S58°E - 25.4'; 8" Oak - S32°W - 22.8'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 7-13-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558