

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---|--|--------------------|
| 1. PUBLIC LAND SURVEY_____ | T. <u>44</u> N. <u>16</u> R. <u>16</u> <u>W.</u> | A-9, A-10 |
| 2. PROPERTY CONTROLLING IN SECTION_____ | , T. _____ N. _____ S., R. _____ E. _____ W. _____ | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION_____ | , T. _____ N. _____ S., R. _____ E. _____ W. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on March 23 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A-9 A. Description of original monument and accessories and/or subsequent restoration:
N.W. section corner of Section 30; Wood Post, Tamarack 7" - N45° E - 10 lks.; Tamarack 5" - N70°W - 82 lks.; Tamarack 5" - S68°E - 55 lks.; Tamarack 6" - N71°E - 139 lks.

A-10 West 1/4 corner - Section 30; Wood Post, Y. Pine 18" - N3°W - 1.06 chs.; no other recorded.

A-9 B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Set by single proportionate measurement from northwest corner of Sec. 18, North and southwest corner of Section 31 south. No sign of original evidence.

A-10 Set M.P.O.L. between the N.W. and S.W. section corners of Section 30. No sign of original evidence.

ALL C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1" pipe, 4" aluminum cap.

A-9 8" Spruce - S79°W - 34.8'; 8" Spruce - N55°W - 28.3'; 15" W. Pine - N56°W - 42.5'; 13" J. Pine - S67°E - 84.0.

A-10 5" R. Pine - N11°W - 67.6'; 9" R. Pine - N1°W - 65.9'; 11" R. Pine - N79°E - 48.6'; 17" W. Pine - N68°E - 41.9'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 7-13-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558