

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 44 N. R. 16 W.	A-1, B-1, C-1
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 24 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-1 N.W. corner - Section 6 (township corner); Wood Post, Tamarack 6 - N4°E - 21 lks; Do 6 - S65°W - 32 lks.; searched but found no sign of either O.B.T.
- B-1 North 1/4 corner - Section 6; Wood Post, Aspen 6 - N18°E - 1.12 chs.; Do 6 - N75°W - 1.25 chs.
- C-1 N.E. section corner - Section 6; Wood Post, B. Ash 5 - N25°E - 42 lks.; Do 6 - N31°W - 31 lks.; Tam. 3 - S63°E - 17 lks.; Tam. 4 - S26°W - 17 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-1 Found old square post not of record but its position fits the stream calls "West 7.45" and "South 6.84." Distances east - west and south to the nearest recoverable corners are reasonable.
- B-1 Set by single prop. measurement to G.L.O. record using township corner 1/2 mile west and 1/4 corner 1 mile east.
- C-1 Set by single prop. measurement to G.L.O. record using the 1/4 corner 1/2 mile east and the township corner 1 mile west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL 1" pipe, 4" aluminum cap.
- A-1 5" B. Spruce - S1°E - 14.7'; 5" B. Spruce - S75°W - 18.5'; 4" R. Maple - S76°E - 21.0'; 6" B. Spruce - N41°E - 23.9'.
- B-1 10" B. Spruce - N3°E - 75.1'; 8" B. Spruce - S82°E - 11.3'; 5" Balsam - S62°E - 16.6'; 12" B. Spruce - S1°W - 18.5'; falls on westerly point of small ridge.
- C-1 9" Cedar - S25°E - 52.6'; 9" Cedar - N75°E - 4.6'; 8" Cedar - S34°W - 45.0'; 13" R. Maple - S65°W - 14.35'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 7-13-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558