

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>16W</u>	<u>A6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>44N</u> R <u>16W</u>	<u>3</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Dec 14 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (A6) Quarter corner common to Section 18 T44N-R16W and Section 13 T44N-R17W. 1981 - Reestablished by proportionate measurement by D.B.Babbitt RLS. Set 1" pipe with 4" aluminum cap. 11" J.Pine N28W 19.15', 4" Spruce S35E 21.25', 8" J.Pine N82E 14.6', 4" Spruce S40W 7.35'.
- (3-Sec. 18) North 1/16 corner between Sec. 18 T44N-R16W and Sec. 13 T44N-R17W. 1981 - Established by D.B.Babbitt midway and on line between Section corner north and Quarter corner south. Set 1" pipe with 4" aluminum cap. 7" J.Pine N28W 10.15', 8" J.Pine S34E 5.4', 9" J.Pine S27W 0.9', 6" Spruce N78E 15.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (A6) Found the 1981 monument in good condition and at record bearing and distance from the 1981 witnesses, now all dead. Left the monument in place and made new witnesses as described below.
- (3-Sec. 18) Found the 1981 monument in good condition and at record bearing and distance from the 1981 witnesses, now all dead. Confirmed the position of the monument with respect to Section and Quarter corner north and south and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--------------------------------------------------------------------|------------------------------------------------------------------------|
| (A6) Found 1" I.pipe with 4" aluminum cap. Set measuring nails in: | (3) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: |
| 8" Maple N23E 22.4' mrkd "1/4S NBT" | 10" J.Pine S82E 16.25' mrkd "N1/16 BT" |
| 5" Maple N65W 12.95' do | 6" twin J.Pine S12W 24.45' do |
| 9" Spruce S70W 36.4' do | 6" J.Pine S51W 30.55' do |
| 7" J.Pine S32W 27.2' do | 7" J.Pine S73W 34.45' do |
| Bearings are magnetic. Distances are to nail with tag. | Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 1/17/07

For the Michigan Department of Natural Resources, Office of Land and Facilities