

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>16W</u>	<u>87</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>18</u> T <u>44N</u> R <u>16W</u>	<u>6</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

Dec 19 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(B7) Quarter corner common to Sections 18 and 19. 1850 - Established by William Ives, Deputy Surveyor: N 89 deg. 45'E corrected between Sections 18 and 19 ...38.02 Set quarter section post. Spruce 5 N61W 10 links, Spruce 4 S31E 3 links. ...77.86 Section corner. (6-Sec. 18) Northeast 1/16 corner, Section 18. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B7) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record, on the Section line between Section corners 2515.09' west and 2635.49' east.  
 (6-Sec. 18) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The position for the corner falls in the South Branch of the Stutts Creek and was not monumented. Set a witness corner on the south side of the creek, on the east N-S 1/16 line, 50.00' south of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B7) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:	(6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap 50.00' south of the corner position. Set measuring nails in:
7" Spruce N81W 22.72' mrkd "1/4S NBT"	17" Cedar S54W 17.35' mrkd "WC BT"
7" Spruce S02W 31.25' do	7" Balsam N46W 18.5' do
7" Spruce S67E 51.4' do	8" Balsam S17W 15.72' do
10" J.Pine N20E 82.6' do	6" Balsam S54E 13.8' do
Bearings are magnetic. Distances are to nail with tag.	Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 1/17/07