

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>16W</u>	<u>D7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>2</u>
3. Miscellaneous Property in Sec.	S <u>20</u> T <u>44N</u> R <u>16W</u>	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

2 Dec 06 2006  
D7 Dec 04 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

[D7] Quarter corner common to Sections 17 and 20. 1850 - Established by William Ives, Deputy Surveyor: S89 deg. 45'W Corrected between Sections 17 & 20 ... [39.84 Quarter corner] Spruce Pine 12 N56E 7 links, Spruce Pine 10 S45W 18 links. ...79.68 Section corner.

[2-Sec. 20) East 1/16 corner between Sections 17 and 20. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

[D7] The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by proportionate measurement to the original record, on the Section line and midway between Section corners 2635.50' east and west.

[2-Sec. 20) Established the corner midway and on the Section line between Quarter corner 1317.75' west and Section corner 1317.75' east. The position for the corner falls in the Stutts Creek and was not monumented. Placed a Witness Corner on the Section line 15.00' West of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

[D7] Set 1"IDx36" I.pipe with 4" alum. IDNR cap. Set measuring nails in:	(2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap 65.00' west of the position for the 1/16 cor. Set measuring nails in:
1" J.Pine S63W 6.57' mrkd "1/4S NBT"	7" J.Pine N70E 5.62' mrkd "WC BT"
1" J.Pine S23W 27.9' do	8" twin J.Pine N38W 1.88' do
1.0" J.Pine S85E 35.0' do	5" J.Pine S03W 6.02' do
1" J.Pine N32E 15.33' do	6" J.Pine S43E 17.78' do
Bearings are magnetic. Distances are to nail with tag.	Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 1/17/07