LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

	Schoolcraft (County)	Located In:	Corner Code ##
1.	Public Land Survey	T 45N_R 13W	_K-5
		T R	
		T #	
		T R	
2.	Property Controlling	S T R	
	in Section	S T R	
3.	Miscellaneous	S T R	
•	Property in Sec.	S , _ T R	

Register of Deeds Stamp & File Number

4. Lot No ______, Recorded Plat

5 Private Claims ______

I. David Babbitt in a field survey on 7/3 19 85 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 - K-5. SE section corner of Section 11. Wood post. Sugar 10, N52°E, 45 Lks. Beech 8, S18°W, 25 Lks.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 - K-5. Set DNR monument at very old farm fence cor. mea. West 1328 to a stream, North 10605 ft. to the section corner common to Sections 1 & 2 on the N. twp. line, South 1815 and 2932 to stream crossings and East 1965' to enter swamp, when compared to the original gov't. survey record all indicate that said fence corner is, in fact, at the original sec. cor. position. I have, therefore, accepted the fence cor. as being the best available evidence of the true sec. cor. position and have monumented it accordingly.
- C Description of monument for corner and accessories established to perpetuate locating the position of the corner

K-5. DNR Monument.

y. birch w/twin top N36°E, 36.85' 5" h. maple S50°E, 53.0' 7" h. maple S79°W, 31.8' 10" h. maple N82°W, 33.7'

Signed by Land B. Balkitt Date

1-5-1989

Surveyor's Michigan License No.

21558

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAM 28, 1571 REVISED MAY 14, 1915 REVISED JAM., 1903