

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SCHOOLCRAFT
(County)

Located In:

Corner Code ≠

1. Public Land Survey	T	<u>45N</u>	R	<u>13W</u>	<u>K-3</u>		
	T	<u>45N</u>	R	<u>13W</u>	<u>L-3</u>		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
2. Property Controlling in Section	S	<u>1</u>	T	<u>45N</u>	R	<u>13W</u>	<u>16</u>
	S	_____	T	_____	R	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gerald L. Wiggins, in a field survey on 6-13 & 6-15, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-3 S.W. Section Corner of Section 1. OBT'S: Sugar 26", N62°E, 9 lks. &
 Sugar 10", S87°W, 32 lks.
 L-3 South 1/4 Corner of Section 1. OBT'S: Beech 14", S49°W, 39 lks. &
 Beech 6", N89°E, 39 lks.

16 East 1/16 Corner on South side of Section 1. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 Corner set by double proportionate measure from found 1 1/2" pipe 1/2 mile West, and Section corners 1 mile North and South and 1 mile East. Distance West to swamp fit original.
 L-3 Corner set midpoint on line between S.W. Section Corner and S.E. Section Corner of Section 1.
 16 Corner set midpoint on line between South 1/4 Corner and S.E. Corner of Section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 DNR Monument set at all three corners.

K-3	10" Maple, N9°W, 10.7'	L-3	8" R. Pine, N10°W, 108.0'	16	6" Maple, S65°E, 11.3'
	5" Maple, N64°E, 20.0'		10" R. Pine, N45°E, 78.1'		4" Maple, S33°E, 9.0'
	6" Maple, S80°E, 22.6'		10" R. Pine, S69°E, 40.3'		14" Maple, S83°W, 19.8'
	5" Maple, S23°W, 8.7'		8" R. Pine, S25°E, 54.6'		10" Maple, N73°W, 4.4'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

Signed by Gerald L. Wiggins
 Surveyor's Michigan License No. 23521

Date 10-14-89

