

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SCHOOLCRAFT

(County)

Located In:

Corner Code -#

1. Public Land Survey	T	<u>45N</u>	R	<u>13W</u>	K-4		
	T	<u>45N</u>	R	<u>13W</u>	J-3		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
2. Property Controlling in Section	S	<u>11</u>	T	<u>45N</u>	R	<u>13W</u>	2
	S	_____	T	_____	R	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gerald L. Wiggins, in a field survey on 6-13 & 6-29, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4 1/4 Corner between 11 and 12. OBT'S: Sugar 16, S13°W, 18 lks & Beech 6, N21°E, 28 lks.

J-3 South 1/4 Corner of Section 2. OBT'S: Sugar 14, N49°E, 41 lks & Y. Birch 12, S16°W, 28 lks.

2 East 1/16 Corner on north side of Section 11. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 Corner set midpoint on line between N.E. Corner and S.E. Corner of Section 11.

J-3 Found 1 1/2" pipe at corner of road west and south, marsh east fits original distance.

2 Corner set midpoint on line between North 1/4 Corner and N.E. Corner of Section 11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 DNR Monument. J-3 1 1/2" Pipe. 2 DNR Monument.

8" Maple, S47°E, 17.8'	12" H. Maple, S69°E, 10.3'	Sq. Scribed 3" Tamarack, S50°E, 1.2'
12" Maple, N84°W, 22.05'	6" H. Maple, N11°E, 31.8'	5" Tamarack, N6°W, 50.3'
7" Maple, N7°E, 25.05'	12" H. Maple, N18°W, 40.2'	4" Spruce, N75°E, 42.0'
5" Maple, N62°E, 13.3'	12" H. Maple, N58°W, 21.3'	6" W. Pine, N23°E, 59.3'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													


Signed by

Surveyor's Michigan License No.

23521

Date

3-12-90



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 ***** REPEALED *****
 REPEALED JAN. 14, 1978
 REPEALED JAN. 1983