

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Washtenaw to K-2
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>45N</u>	R	<u>13W</u>	<u>K-2</u>		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
2. Property Controlling in Section	S	<u>1</u>	T	<u>45N</u>	R	<u>13W</u>	<u>3</u>
	S	<u>1</u>	T	<u>45N</u>	R	<u>13W</u>	<u>10</u>
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Gerald L. Wiggins, in a field survey on 6-15, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2 West 1/4 Corner of Section 1. OBT'S: Beech 10, N48°E, 26 lks. & Sugar 6, S65°W, 14 lks.

3 North 1/16 on west side of Section 1. Not previously set.

10 South 1/16 on west side of Section 1. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 Corner set by single proportionate measure between N.W. Corner and S.W. Corner of Section 1.

3 Corner set by single proportionate measure between West 1/4 Corner and N.W. Corner of Section 1.


10 Corner set midpoint on line between West 1/4 Corner and S.W. Corner of Section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 DNR Monuments placed at all three corners.

K-2	12" Maple, N70°W, 9.7'	3	14" Cedar, S70°E, 4.3'	10	8" Y. Birch, S70°E, 24.5'
	6" Maple, S74°E, 1.0'		12" Cedar, S11°E, 16.6'		14" Beech, N5°E, 3.3'
	7" Maple, S24°E, 15.5'		10" Cedar, S66°W, 17.7'		12" Beech, S55°E, 29.0'
	8" Maple, S38°W, 10.0'		10" Cedar, N45°W, 19.8'		10" Maple, S18°W, 6.7'

Cor. lies west side of trail road.

Signed by Gerald L. Wiggins Date 3-12-90
 Surveyor's Michigan License No. 23521



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971
 REVISED MAY 14, 1978
 REVISED JAN. 1983