

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>13W</u>	<u>L5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>15</u>
	S <u>12</u> T <u>45N</u> R <u>13W</u>	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	<u>L5</u> Oct 15 2003	
	<u>15</u> Oct 13 2003	

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (L5) Quarter corner common to Sections 12-13. 1986: Gerald L. Wiggins RLS reestablished the corner midway and on line between Section corners. Set 1"IDx36" I.pipe with 4" aluminum MDNR cap. 7" Cedar N44W 5.9', 6" Cedar S41W 18.3', 7" Cedar S06E 20.7', 6" Cedar S55E 11.4'
- (15-Sec. 12) West 1/16 corner between Sections 12 and 13. Not established in the original survey. Found no record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (L5) Recovered the 1986 monument in good condition and at record bearing and distance from the 1986 witness trees. The monument is not accepted due to the fact that Mr. Wiggins did not properly monument corner M5, upon which the location of this corner depends (see LCRC L3 P942, Luce Co. Records) I reestablished L5 midway and on a line of mean true bearing between Section corners of record 2651.20' East and West.
- (15-Sec. 12) Established the corner midway and on a line of mean true bearing between Section corner of record 1325.60' West and Quarter corner (as reestablished by the undersigned) 1325.60' East. From the corner thus established, I found a 1/2" iron bar, set by an unknown party S9W 3.8' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (L5) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set nails/tags in: | (15) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Blazed, scribed, and set
measuring nails in: |
| 10" Cedar S30E 23.45' (1986 NBT) | 5" Maple N68E 7.75' "W1/16 BT" |
| 12" Cedar S06E 34.2' do | 7" Maple N03W 31.1' do |
| 10" Cedar S21W 28.4' do | 7" Maple N81W 38.55' do |
| Blazed and scribed: | 6" Ironwood S54W 38.7' do |
| 10" Cedar S12W 8.65' "1/4S NBT" | Bearings are magnetic. Distances are to
nail with tag. |
| 10" Cedar N70W 9.6' do | |
| Set a sq'd and scribed post adjacent. | |
| Bearings are magnetic. Distances to
nail with tag. | |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/19/03

For the Michigan Department of Natural Resources, Office of Land and Facilities