

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>45N</u> R <u>13W</u>	<u>K5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Aug 19 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


(K5) Corner common to Sections 11-12-13-14. Reestablished at old farm fence corner in 1985 and recorded in 1989 by David B. Babbitt, RLS. 1" pipe with 4" dia. aluminum cap (DNR monument). Y. Birch w/twin top N36E 36.85', 5" H. Maple S50E 53.0', 7" H. Maple S79W 31.8', 10" H. Maple N82W 33.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K5) Recovered the 1985 monument, a 1" ID iron pipe capped with a 4" dia. cast aluminum MDNR tablet, in good condition, and at record bearing and distance from the remaining two 1985 witness trees, H. Maples NW and SW. Left the monument in place and made new witnesses as described below. The corner lies to the NW of a trail intersection with trails proceeding West, North, and Southeast.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K5) Found 1" pipe with 4" alum. cap.
 Blazed, scribed, and set measuring nails in the following:
 10" Ash S58E 65.2' "S13 NBT"
 10" Sugar N84E 58.5' "S12 NBT"
 Placed meas. nails in the 1985 wits:
 8" Sugar S82W 32.0'
 12" Sugar N80W 33.6'
 Placed a 3" squared cedar post adjacent.
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 11/19/03
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities