

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 & 46 N.R. 16W

Schoolcraft COUNTY


DESCRIPTION OF CORNER 4 Corner for Sections 31 T46N, R16W

6 T45N, R16W

CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9-8-61

WITNESSES TO CORNER..... 5" W. Pine (1/4 S NBT) N60°E 64 1/2 links



4" W. Pine (1/4 S NBT) N65°W 62 1/2 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from original B.T. (4" W. Pine N50°E, 24 links) 4" Spruce gone. Face nearly gone. Iron marks on edge of face and notch visible on W.Pine stump.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE January 2, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler