

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 16. W.

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 16-17-20-21

DESCRIPTION OF CORNER MONUMENT 2" pipe with brass cap

WITNESSES TO CORNER 11" Cedar S 54° Wc 37 links  
"S 20 N BT"

5" Cedar S 4° E 73 links  
"S 21 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

One cedar B.T. bears S 46° E 16 links. Tree standing in excellent condition. Winter roads running north and east of corner.

This B.T. has been used as the true corner for running cutting lines in this area.

Shown to us by Jack Zollner, Ass't Forester.

Re-Witnessed corner as set by Carl Christensen, Manistique.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 3/1/57  
REGISTERED LAND SURVEYOR