

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner for sections 22-23-26-27

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/26/63 by A.O. Enger - 5/19/65 recorded and
Monumented by Bray and Hinds.

WITNESSES TO CORNER..... 7" Jack Pine (S22 NBT), N 30° W, 52½ lks.



19" Red Pine (S26 NBT), S 65° E, 121 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set from one Original BT, W. Pine 18", S 60° W, 50 lks. BT is 5" sawed off stub. Axe marks and overgrowth plain, but scribe marks weathered off. Distance North to swamp edge and river checks. Does not check to River to East as river course has changed.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965
REGISTERED LAND SURVEYOR