

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Secs. 35-36

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/24/63 by A.O. Enger -- 5/19/65 recorded and
Monumented Bray and Hinds.

WITNESSES TO CORNER..... 8" Red Oak (1/4S (NBT), S 77° E, 19 1/2 Lks.



8" W. Birch, (1/4S NBT), S 06° E, 34 1/2 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set from two stump bottoms and in agreement with Original BT's as to species, size, bearing and distance from corner. Corner is 39.91 Chs North of Original Section Corner on Township Line. Distance North to stream checks closely. Corner found by Foresters W.J. Wallace and A.O. Enger -- 4/19/63.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965
REGISTERED LAND SURVEYOR