

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 46 N.R. 13W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 5-6-7-8

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 8-9-61 with Wm. Miller, aide

WITNESSES TO CORNER..... 3" Tamarack (X) N50°W 15 links



3" B. Spruce (X) S85°E 04½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportionate measure from corners ½ mile south; 1 mile north; ½ mile west and ½ mile east.

Note: Corner lies in wet spruce swamp about 3 chains ½ south of high ground.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE December 28, 1961  
REGISTERED LAND SURVEYOR  
Billy D. Buckler