

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46N N.R. 13W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/2 Corner between Sections 17-20

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 8-10-61 with Wm. Miller, aide

WITNESSES TO CORNER..... 13" Cedar (1/4 S NBT) S17°W 12 links



12" Cedar (1/4 S NBT) S73°E 17 1/2 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established midway and on line between an original Section Corner 1/2 mile west and a Hwy. Dept. Section Corner 1/2 mile East.
No evidence of original corner. Found old blazes both east and west of corner.

Corner lies in Cedar swamp.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE December 28, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler