

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N. R. 13W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Corner between Sections 19-30

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 8-10-61 with Wm. Miller, aide

WITNESSES TO CORNER..... 8" Jack Pine (S NBT) N60°W 54½ links



8" Jack Pine (S NBT) S1° W 50½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Y.Pine stump (probable B.T.) bearing N72°E 46 links.
Stump badly burned.

Corner lies on South side of narrow Jack Pine ridge.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE December 28, 1961