

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 46 N.R. 13W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19-20-29-30

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 8-14-61 with Wm. Miller, aide

WITNESSES TO CORNER..... 10" Elm (S20 NBT) N64°E 19½ links



14" Cedar (S30 NBT) S43°W 104 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportionate measure from corners ½ mile west; 1 mile South; 1 mile North and 1 mile East. Found recent blazes and wood stake about 40 links east of corner.

SURVEYOR'S SEAL

SIGNED Billy O. Buckler DATE December 28, 1961  
REGISTERED LAND SURVEYOR