

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

SCHOOLCRAFT CO.

3 CORNERS.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>46</u> N. R. <u>13</u> W.	<u>I-2, K-2, J-2</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ S. R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ S. R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-14 & 6-20, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-2 West 1/4 Corner of Section 2. OBT'S: Cedar 12", N17°W, 103 lks. & Spruce 8", S14°E, 128 lks.
- K-2 East 1/4 Corner of Section 2. OBT'S: W. Pine 10", N30°W, 63 lks. & Beech 8", S5°E, 56 lks.
- J-2 Center of Section 2. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-2 Corner set by single proportionate measure between N.W. Section Corner and the S.W. Section Corner of Section 2. Corner fits a down and rotted Cedar that in 1952 was described as an original B.T. No marks could be found at this time.
- K-2 Corner set by single proportionate measure between N.E. Corner and S.E. Corner of Section 2.
- J-2 Corner set at intersection of N-S and E-W 1/4 lines of Section 2.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument set at all three corners.

- | | | |
|----------------------------|--------------------------|-------------------------------|
| I-2 6" Cedar, N25°W, 35.2' | K-2 36" W. Pine | J-2 12" Hemlock, N20°E, 26.7' |
| 6" Cedar, N4°E, 15.2' | Stump, S78°E, 71.4' | 12" Hemlock, S44°E, 15.45' |
| 6" Cedar, S44°E, 5.9' | 8" Maple, N26°E, 16.0' | 16" Hemlock, S25°W, 25.0' |
| 8" Cedar, S4°E, 6.4' | 7" W. Pine, N28°E, 42.7' | 8" Hemlock, N86°W, 45.95' |
| | 9" W. Pine, S31°E, 36.2' | |

SIGNED BY Gerald L. Wiggins
Gerald L. Wiggins
 SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

DATE 8-11-88



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
 REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET