

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

SCHOOLCRAFT CO.

3 CORNERS.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>46</u> N. R. <u>13</u> W.	<u>K-3, J-3, L-3</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-20, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-3 S.E. Corner of Section 2. OBT'S: Birch 16", N50°W, 33 lks. & Beech 10", S40°E, 4 lks.
 J-3 South 1/4 Corner of Sec. 2. OBT'S: W. Pine 24", N88°W, 98 lks. & No other near.
 L-3 South 1/4 Corner of Sec. 1. OBT'S: Hemlock 12", N48°E, 62 lks. & Birch 12", S5°W, 23 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-3 Corner set by double proportionate measure between Section Corners 1 mile North, East, and West and Stream South.
 J-3 Corner set midpoint on line between S.W. Corner and S.E. Corner of Section 2.
 L-3 Corner set midpoint on line between S.E. Corner and S.W. Corner of Section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monuments set at all three corners.

- | | | |
|--------------------------------|----------------------------|----------------------------|
| K-3 14" W. Birch, N76°E, 69.2' | J-3 4" Aspen, N20°W, 15.0' | L-3 7" Maple, N51°W, 41.5' |
| 7" Maple, N38°E, 32.5' | 6" Spruce, N47°E, 45.9' | 8" Maple, S56°W, 32.2' |
| 7" Maple, N57°W, 29.3' | 14" R. Pine, S30°W, 41.8' | 8" Maple, S38°W, 27.1' |
| 8" Aspen, N72°W, 58.5' | 5" J. Pine, S64°W, 65.6' | 7" Maple, S32°E, 20.9' |


SIGNED BY Gerald L. Wiggins DATE 8-8-88

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 20, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET