LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Schoolcraft			
_	(County)	Located In:	Corner Code ##
1.	Public Land Survey	T 46N R 13N	D9
		T R	
		T R	
		Ť R	
2.	Property Controlling	S29 T _46H R _13N_	_13
	in Section	S T R _	
3.	Miscellaneous	S T R	
	Property in Sec.	S T A	

Register of Deeds Stamp & File Number

4. Lot No. ______ , Recorded Plat ,

5. Private Claims __

I. Stephan J. Szyszkoski in a field survey on September 20, 1994 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(09) Quarter corner common to Sections 20-29. Corner reestablished in 1961 by Billy D. Buckler RLS, as follows: "This corner was reestablished midway and on line between two section corners. No evidence of original corner. Corner lies in thick alder marsh. Corner monument 1" pipe with 4" brass cap. Witnesses: 8" tamarack S62E 27.5 links, 6" tamarack H33M 61.5 links." Found no subsequent record.

(13-Section 29) WITNESS CORMER to the Southeast 1/16 corner, Section 29. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

(D9) Recovered the 1961 monument, a 1" iron pipe capped with a 4" brass Michigan Dept. of Conservation cap, as described, in good condition, and at record bearing and distance from the 1961 MBTs. The 8" tamarack is in good condition and now 10" diameter. The 6" tamarack is dead. Left the monument in place and marked three new witnesses as described below.

(13-Sec. 29) Found no evidence of previous monumentation at the corner position. The corner itself falls in the Fox River. I established the corner at the intersection of straight lines connecting opposite 1/16 corners. The 1/16 corners to the north and east being monumented, and those to the south and west computed positions midway and on a straight line between appropriate section and quarter corners. I did not place a monument at the corner position, but placed a MITNESS CORNER 118.36' north of the corner on the 1/16 line. The present north stream bank is 62' south of this location. At the position for the corner, I placed a 1" 1.0.x36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. The witness corner is 1196.62' south of the monumented east 1/16 corner of the section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D9) found 1 iron pipe with 4 brass cap. Blazed, scribed, and set measuring nails in the following:

5" Tamarack M86E 57.3' "1/45 MBT" "1/45 MBT" "1/45 MBT"

3" Tamarack \$83E 67.4" 1/45 MBT" 8" Tamarack \$34E 9.5" 1/45 MBT" 8marings are magnetic.

(13-witness corner) Set 1° iron pipe with 4° MDNR cap. Blazed, scribed, and set measuring nails with tags in the following bearing trees:

clump 14" Maple M81E 69.55" "MC 87" clump 14" Maple S85E 21.8" "MC 87" 6" Maple S10E 37.6" "MC BT"

6° Elm M61E 54.9° "MC BY" Placed a 5' squared and scribed cedar post adjacent. Bearings are magnetic. STEPHAN J. SZYSZKOSKI LAND SURVEYOR No. 33986

Signed by Stephan J. Soughfool.

12-7-799000

For the Michigan Department of Matural Resources - Forest Management Division.

For the Michigan Department of Matural Resources - Forest Management Division.

REVISED MAN. 1983

REVISED MAN. 1983