

62

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft

(County)

Located in:

Corner Code #

1. Public Land Survey

T 46N R 13W

611

T 46N R 13W

612

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Aug 11 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11							●						
12	31		32		33		●		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

(G11) Corner common to Section 27-28-33-34. Corner replaced in 1970 by Billy D. Buckler, RLS, from local evidence. Corner perpetuated with a 1" pipe with 4" aluminum cap and the following NBTs: 11" R. Pine S32W 101.7', 11" R. Pine S57E 87.8'.

(G12) Quarter corner common to Sections 33-34. Corner perpetuated from probable original BT in 1970 by Billy D. Buckler, RLS. Description of new monument not included on 1970 recordation certificate but was certainly a 1" iron pipe capped with a 4" dia. aluminum MDNR tablet. 1970 witness is a 9" Soft Maple S29W 112.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G11) Recovered the 1970 monument as described, in good condition, and at record bearing and distance from the Red Pine NBT S32W, in good condition, now 14" dia. The R.Pine SE has been cut. Left the monument in place and marked new witnesses as described below. Corner recovered and re-witnessed by T. Stark, Newberry District Office.

(G12) Recovered a 1" I.D. iron pipe capped with a 4" dia. cast aluminum MDNR tablet, in good condition, and at record bearing and distance from the 1970 witness maple. Accepted same as a careful and faithful perpetuation of the position of the original corner. Left the monument in place and marked three new witnesses as described below. Corner recovered and re-witnessed by T. Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


(G11) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:

12" R. Pine S02W 30.55' "S33 NBT"  
5" Tamarack S31E 31.7' "S34 NBT"  
5" J. Pine N18E 11.45' "S27 NBT"  
6" J. Pine N85W 29.5' "S28 NBT"

Bearings are magnetic.

(G12) Found 1" pipe with 4" MDNR cap. Blazed scribed and set measuring nails in the following:

14" Maple S28W 113.3' "1/4S"  
4" Aspen S03E 26.8' "1/4S NBT"  
4" J. Pine N48W 20.4' "1/4S NBT"  
4" J. Pine N22W 14.75' "1/4S NBT"  
Placed a 4" squared and scribed cedar post adjacent.



Signed by

Stephan J. Szyszkoski

Date

8/27/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division