

63

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T 46N R 13W	H13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 34 T 46N R 13W	5
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

5 Aug 21 1997
H13 Aug 19 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(H13) Quarter corner common to Sections 34 T46N-R13W and 3 T45N-R13W. Corner re-monumented in 1970 by Billy D. Buckler, RLS, "This corner replaced as set by the U.S. Dept. of Agriculture while running the boundaries of the Seney Wildlife Refuge. Found a scribed 6" Tamarack bearing, N18W 13.9'. Found bottom of a wood post, in ground at the corner. 1" pipe with 4" aluminum cap. 5" Cedar S25W 4.6', 6" Cedar S79W 19.9". The undersigned tried and was unable to gather field notes or maps from the U.S. Fish and Wildlife Service pertaining to the US Dept. of Agriculture (Biological Survey) survey of the Seney Refuge. It is not known where Buckler learned of the USBS work.

(5-Sec. 34) North 1/16 corner, Section 34. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H13) Recovered the 1970 monument as described, in good condition, and at record bearing and distance from the remains of the 1970 witness cedars, now both cut stumps. No USBS monumentation was recovered. I determined that the monument is 1.07' North and 0.74' East of the proportionate position and I accept the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked new witnesses as described below. Corner recovered and re-witnessed by T.Stark, Newberry District Office.

(5-Sec. 34) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1312.43' North and Center of Section 1312.43' South. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position:

(H13) Found 1" Pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:	(5) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:
14' Cedar, North 11.45' "1/4S NBT"	3" Tamarack S69E 5.2' "N1/16 BT"
5" Cedar S87E 8.2' "1/4S NBT"	4" Tamarack S88E 1.7' "N1/16 BT"
6" Cedar S25E 26.0' "1/4S NBT"	3" Spruce N49N 1.8' "N1/16 BT"
8" Cedar S05E 19.95' "1/4S NBT"	4" Spruce N20W 20.9' "N1/16 BT"
4" squared and scribed post adjacent. Bearings are magnetic.	Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 8/27/98
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division