

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 46N R 13W	C8
	T _____ R _____	(GCDB 200340)
	T 46N R 13W	B7
2. Property Controlling in Section	S T _____ R _____	(GCDB 140400)
	S T _____ R _____	
	S T _____ R _____	
3. Miscellaneous Property in Sec.	S T _____ R _____	
	S T _____ R _____	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7		●											
8		19	●	20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on C8 08/26/14
B7 08/06/14 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(C8) Quarter corner common to Sections 19 and 20. 1961 - Reestablished by Billy D. Buckler RLS,
midway and on line between two Section corners. No evidence of original corner. Corner lies in
open marsh. Set 1" pipe with 4" brass cap. 5" Tamarack N60°E 87.5 links.

(B7) Quarter corner common to Sections 18 and 19. 1961 - Billy D. Buckler RLS remonumented the
corner position at record bearing and distance from an original W.Pine BT N10°E 48 links, a stump in
poor condition. Set 1"ID I.pipe with 4" brass cap. 9" R.Pine N72°W 36.5 links, 10" J.Pine S40°W
06.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C8) Found the 1961 monument in good condition and at an erroneous position 97.30' north of that
intended by Mr. Buckler in 1961. After examining the 1961 field notes, I conclude that Mr. Buckler
mistakenly measured north from his temporary position, rather than south, as he intended to do,
resulting in the position being monumented incorrectly. The monumented position does not appear to
have been relied upon in the intervening years. I therefore destroyed it and reestablished the
position midway and on the Section line between Section corners 2611.89' north and south,
proportionate to the original record of 39.82 chains north and south, and in accord with the 1961
method.

(B7) Found the 1961 monument in good condition and at record bearing and distance from the 1961
witnesses. The R.Pine N72°W is green, the J.Pine S40°W is dead and down. Accepted the monument as
a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C8) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
3" W.Pine S21°E 74.85' mrkd "X"
7" Tamarack N32°E 137.5' "1/4S"
3" W.Pine N43°E 106.95' "X"
3" W.Pine S87°W 193.25' "X"
E= 8079266.041 N= 176544.072

(B7) Found 1"ID I.pipe with 4" brass MI Dept. of
Conservation cap. Set measuring nail with MDNR
tag in the side of:
20" R.Pine N69°W 24.7' mrkd "1/4S" (1961 NBT)
8" R.Pine S41°W 31.9' "1/4S NBT"
6" Balsam N21°E 7.05' do
11" J.Pine S01°W 22.75' do
E= 8078447.156 N= 177339.518

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011)) Date
Coord. Ref.=NGS PID RJ1233: N= 183112.192 m. E= 8082067.781 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 09/04/2014

For the Michigan Department of Natural Resources, Forest Resources Division

