

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Schoolcraft

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

(County)

- |                                    |                                      |           |
|------------------------------------|--------------------------------------|-----------|
| 1. Public Land Survey              | T <u>46N</u> R <u>13W</u>            | <u>83</u> |
|                                    | T _____ R _____                      | _____     |
|                                    | T _____ R _____                      | _____     |
|                                    | T _____ R _____                      | _____     |
| 2. Property Controlling in Section | S <u>7</u> T <u>46N</u> R <u>13W</u> | <u>1</u>  |
|                                    | S _____ T _____ R _____              | _____     |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____              | _____     |
|                                    | S _____ T _____ R _____              | _____     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1 Nov 06 2002  
 B3 Nov 04 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3	•	•										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 (B3) Quarter corner common to Sections 6-7. 1850: Established by Guy Carleton: S89 deg 22'E corrected...37.84 Set quarter post. Hemlock 16 S15E 28 links, Tamarac 12 N79W 5 links...78.00 Section corner. 1953: recovered by Dean C. DeLaMater, RLS: This corner was pointed out to me by F.C. Hall, District Forester, of Munising. Corner had been previously set by unknown surveyor. One original B.T. still in place, good condition. 2" pipe with 2" brass cap. 8" Tamarack S60E 22 links, 6" W.Pine S70W 29 links.  
 (1-Sec. 7) West 1/16 corner between Sections 6 and 7. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (B3) Recovered the monument of record, a 2" iron pipe with a 2" brass cap, probably placed by Carl Christiansen, stamped "CC 1/7 6/7", in good condition, and at record distance from the 1953 NBTs, both in good condition with overgrown blazes. The Tam was found at S45E, 15 deg. different than the record, the bearing to the W.Pine checks. Distances West and East to adjacent section corners were found 37.372 chains and 39.947 chains, respectively. Accepted the monument for the corner, made new markings on the 1953 NBTs, and marked two new accessories as described below.  
 (1-Sec. 7) Established the corner 20.08 chains, proportionate to the original record, west of the 1/4 corner B3 and on a line of mean true bearing between monumented corners B3 and A3, which are 1308.90' east and 1157.67' west, respectively.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (B3) Found 2" I.Pipe with 2" brass cap. Blazed, scribed, and set measuring nails in:  
 12" Tamarack S45E 14.5' "1/4S" \*  
 12" W.Pine S71W 19.1' do \*  
 6" Spruce N70W 8.55' "1/4S NBT"  
 6" Spruce N26E 15.3' do  
 Set cedar post adjacent. Bearings are magnetic. Distances to nail with tag.  
 \* denotes 1953 NBT.  
 (1) Set 1" IDx36" I.pipe with 4" dia. alum. MDNR cap. Blazed, scribed, and set measuring nails in:  
 7" B.Spruce N37E 18.45' "W1/16 BT"  
 7" B.Spruce S49E 4.6' do  
 6" B.Spruce S08E 10.75' do  
 10" Cedar S87W 8.35' do  
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/3/02