

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft
 (County)

Located In:	Corner Code #
1. Public Land Survey	T ___ R ___
	T ___ R ___
	T ___ R ___
	T ___ R ___
2. Property Controlling in Section	S <u>8</u> T <u>46N</u> R <u>13W</u> <u>13</u>
	S <u>8</u> T <u>46N</u> R <u>13W</u> <u>14</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___
	S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

14 Nov 07 2002
 13 Nov 25 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (13-Sec. 8) Southeast 1/16 corner, Sec. 8. Not established in the original survey.
 (14-Sec. 8) South 1/16 corner between Sections 8-9. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (13-Sec. 8) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. 1/16 corners 12 and 16 were left unmonumented in this survey.
 (14-Sec. 8) Established the corner midway and on a line of mean true bearing between Section corner 1314.27' South and Quarter corner 1314.27' North. The corner falls in State Highway M-77.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1"IDx36" I.pipe with 4" dia. alum. MDNR cap. Blazed, scribed, and set measuring nails in: 11" B.Spruce S66W 12.6' "SE1/16 BT" 12" B.Spruce S78E 44.2' do 10" B.Spruce N12E 23.7' do 10" B.Spruce N57E 35.05' do Bearings are magnetic. Distances are to nail with tag.	(14) Set 1"IDx36" I.pipe with plastic cap # 33986. Blazed, scribed, and set measuring nails in the following trees: 8" Tamarack N74W 49.05' "S1/16 BT" 8" Tamarack N43W 65.55' do 8" Spruce S46W 86.3' do P.Pole 201/74 N66E 80.7' nail w/tag. Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/3/02