

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>13W</u>	D5
	T <u>46N</u> R <u>13W</u>	C4
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 04 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7	●	8		9		10		11		12	
5			●									
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (D5) Quarter corner common to Sections 8-17. Remonumented in 1956 by Billy D. Buckler RLS: Replace corner from one tamarack B.T. in excellent condition. Corner found by Ken Killmar. Corner placed and witnessed January 16, 1956. 1" pipe with 4" brass cap. 10" Cedar S16E 24 links, 9" Cedar S37W 30 links.
 (C4) Quarter corner common to Sections 7-8. 1961: Record of Billy D. Buckler RLS: This corner was re-witnessed as set by Carl Christiansen, Manistique. Found evidence of both Tamarack B.T.'s in proper position. 2.5" pipe with 2.5" brass cap. 5" Tamarack S87W 24 links, 6" B.Spruce N17W 22.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D5) Recovered the 1956 monument in good condition, and at record bearing and distance from the 1956 cedar NBTs, both in good condition. Put measuring nails in the two cedars and marked two new accessories, as described below.
 (C4) Found the monument of record, as described, in good condition, at record bearing and distance from the 1961 NBTs, both in good condition. Left the monument in place and marked two new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D5) Found 1" ID I. pipe with 4" brass MI Dept. of Conservation tablet. Blazed, scribed, and set measuring nails in: 13" Cedar S20E 16.45' "1/4S NBT" * 11" Cedar S40W 20.15' do * 6" Cedar N25E 19.9' do 5" B.Spruce S72W 7.3' do Bearings are magnetic. Distances are to nail with tag. * denotes 1956 NBT.	(C4) Found 2.5" I. pipe with 2.5" brass cap. Blazed, scribed, and set measuring nails in: 6" Tamarack S84W 16.0' "1/4S" * 7" B.Spruce N16W 14.75' old blazes * 4" B.Spruce S24W 28.2' "1/4S NBT" 7" B.Spruce S40E 31.5' do Bearings are magnetic. Distances are to nail with tag. * denotes 1961 NBT.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/3/02