

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46. NR. 14. W.

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3, 4, 9, 10

DESCRIPTION OF CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

WITNESSES TO CORNER 15" W. Pine (S 4 NBT) N 65° W 41 Links

13" W. Pine (S 3 NBT) N 35° E 38 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two probable B.T.'s. Yellow Pine stump bearing N 77° E 33 Links and a White Pine stump, S 32° W 35 Links. Position checks with other corners in area. Found old blazes on White Pine (down) about 4.00 chains south of corner. Corner found while making a partial retracement survey of area.

Corner was placed and witnessed April 21, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 5/18/60