

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46N N.R. 14W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 26-27

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-2-62

WITNESSES TO CORNER..... 8" red pine (1/4 S NBT) N42°E, 40 links



CIRCLE CORNER REGISTERED

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established midway and on line between two section corners. No evidence or original corner.

Corner lies 63 links north of power line.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE July 19, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler