

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46N N.R. 14W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 24-25

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 12-19-62

WITNESSES TO CORNER..... 18" Red Pine (1/2 S NBT) S96°W, 26 links



10" Red Pine (1/2 S NBT) S79°E, 62 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established midway and on line between two section corners. No evidence of original corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 26, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler