

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 13 - 14 W

Schoolcraft COUNTY


DESCRIPTION OF CORNER Section Corner common to Sections 7-18-12-13

CORNER MONUMENT 1" Pipe with 1/4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6-15-62

WITNESSES TO CORNER..... 9" Jack Pine (S 13 NBT) S 35° W 90 links

6" Jack Pine (S 18 NBT) S 30° E 64 links



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportionate measure from corners 1 mile North; 1/2 East; 3 miles South and 3 1/2 miles West.

No evidence of original Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4-2-61
REGISTERED LAND SURVEYOR
Billy D. Buckler