

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 13 - 14 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 24-25-19-30

CORNER MONUMENT 1" Pipe with 1/4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6-18-62

WITNESSES TO CORNER..... 20" Jack Pine (S 30 NBT) S 15° E 58 links



8" Jack Pine (S 19 NBT) N 70° E 13 1/2 links

Corner lies 85 links East of ditch

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by single proportionate measure from Corners 2 miles North and 1 mile South.

No evidence of original Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4-2-64
REGISTERED LAND SURVEYOR
Billy D. Buckler